



PENREN /C this Week



February 23, 2004



Wedges 2-5 Renovation

Wedges 2 through 5 encompass 4.5 million square feet of Pentagon space to be renovated by 2010.

Demolition Progress on Wedge 2, Phase III...



Construction debris, sorted and waiting in AE Drive. Much of the debris will be recycled.



A view of the 2nd floor A ring, stripped out and bare as a field engineer establishes construction control lines.



Demolition crews working along the C-Ring in Corridor 6.

More info on this project can be found at:

<http://renovation.pentagon.mil/wedge2-5/projects-W2-5.htm>



Intake/Outfall

A new intake water line will supply condenser water to the Pentagon air conditioning chillers and the outfall line dispenses warmed condenser water into a local waterway.

The elevated slab is placed over the Screen House sump pit. The slab needs to be finished before installing the traveling screens and screen wash pumps.



Workers placing concrete slab (top) and precast beams (right) at the Screen House.



A total of four pre-cast beams were installed to support the elevated concrete slab placed over the Screen House Sump Pit.

More info on this project can be found at:
<http://renovation.pentagon.mil/projects-IO.htm>



Pentagon Renovation & Construction Program Office
"MEET THE RENOVATORS"

Marvin Miller,
Design & Construction Coordinator, Wedges 2-5

Marvin's role is to provide daily oversight in several areas of the renovation effort, including, design and requirements integration, space management, relocation planning and equipment certification. He also conducts regularly scheduled tenant walkthroughs to insure that the agencies' requirements are met.

In his own words: "My job is unique in that I get to be involved with the project from design to completion, and I actually get to feel the sense of ownership."



For more information on the Pentagon Renovation & Construction Program Office, visit our web site

<http://renovation.pentagon.mil>

Questions & Comments
866.349.0616